



Office of the Bids and Awards Committee

August 26, 2026

SUPPLEMENTAL/BID BULLETIN (SBB) NO. 2026-30

This SBB No. 2026-30 for Project ID No. GS-2026-01.1EPA, ***“Supply, Delivery and Installation of Sound Panel System (Soundproofing Installation).”*** is issued pursuant to Section 51.4 of the Implementing Rules and Regulations of Republic Act No. 12009 (New Government Procurement Act), to clarify, modify or amend items in the Bidding Documents. Accordingly, this shall form an integral part of the Bidding Document.

NO.	PARTICULARS	AMENDMENT
NO.	DESCRIPTION	DESCRIPTION
	GENERAL FUND	GENERAL FUND
	PR NO. 1078 CBM	PR NO. 1078 CBM
1	Sound Panel System (Soundproofing Installation) for a 300-capacity conference hall. Sound room acoustic treatment requirement. a. Acosutic Materials: Fabric Wrapped Soft Acoustic Panel 150 pcs-Thickness: 25mm, Size: 1000x1000mm Finish: Grey Fabric. Diffuser 60 set- Thickness: 100mm, Size: 600x600mm, Finish: Solid Wood b. Services: Installation of Fabric Wrapped Acoustic Panels (150 pcs) Site inspection and verification of installation locations. Layout marking and positioning based on approved drawings. Installation of client-supplied Fabric Wrapped Acoustic Panels including mounting hardware and accessories. Alignment, leveling, trimming, and secure fixing of panels. Final inspection, cleaning, and turnover. Installation of Acoustic Diffusers (60 sets) Site inspection and verification of diffuser locations. Layout marking and positioning based on approved drawings. Installation of client-supplied Solid Wood Acoustic Diffusers including mounting hardware and support brackets. Alignment, leveling, and secure fixing of diffuser assemblies on walls and/or ceilings. Final inspection, cleaning, and turnover. General Services Mobilization and demobilization of manpower, tools, and equipment. Provision of ladders, scaffolding, and installation tools as required. Daily housekeeping and disposal of installation debris. Testing, inspection, and project turnover.	Sound Panel System (Soundproofing Installation) for a 300-capacity conference hall. Sound room acoustic treatment requirement. a. Acoustic Materials: Fabric Wrapped Soft Acoustic Panel 150 pcs-Thickness: 25mm, Size: 1000mmx1000mm. Finish: Grey Fabric. Diffuser 60 set- Thickness: 100mm, Size: 600mmx600mm, Finish: Solid Wood b. Services: Installation of Fabric Wrapped Acoustic Panels (150 pcs) Site inspection and verification of installation locations. Layout marking, positioning, and drawings shall be subject to the approval of the end-user prior to the implementation of the project. Installation of client-supplied Fabric Wrapped Acoustic Panels including mounting hardware and accessories. Alignment, leveling, trimming, and secure fixing of panels. Final inspection, cleaning, and turnover. Installation of Acoustic Diffusers (60 sets) Site inspection and verification of diffuser locations. Layout marking and positioning based on approved drawings. Installation of client-supplied Solid Wood Acoustic Diffusers including mounting hardware and support brackets. Alignment, leveling, and secure fixing of diffuser assemblies on walls and/or ceilings. Final inspection, cleaning, and turnover. General Services Mobilization and demobilization of manpower, tools, and equipment. Provision of ladders, scaffolding, and installation tools as required. Daily housekeeping and disposal of installation debris. Testing, inspection, and project turnover. Supply, installation and commissioning Additional requirement: Site inspection certificate

For guidance and information of all concerned.

REY F. POLON

BAC, Vice-Chairperson for Goods and Services